



**NATIONAL INSTITUTE OF TECHNOLOGY  
HAZRATBAL, SRINAGAR- 190006 (J&K)  
(Planning & Development Wing)  
Tel: 0194-2102157 Fax: 0194-2420475**

**Short term tender Notice No. 01 of 2019**

For & on behalf of Chairman Board of Governors NIT Srinagar, sealed tenders affixed with a revenue stamp of Rs. 10/- are invited from **Civil Contractors** registered with state PWD, CPWD, MES for the below mentioned work:-

<b>Sr.No</b>	<b>Particulars of Items</b>	<b>Cost of work</b>	<b>Earnest money</b>	<b>Completion period</b>	<b>Class of contractor</b>	<b>Cost of T.D</b>
<b>1.</b>	Construction of Shed (20'x40') for Kitchen in Pre-fab hostel.	Rs. 14.45 lacs	Rs. 28,900/-	30 days	B, C & D class	Rs.500/-

**TERMS & CONDITIONS:-**

1. The tenders addressed to Dean P&D, NIT Srinagar, 190006 (J&K) should reach his office on or before **30-01-2019** by Speed Post up to **2.00 P.M.**
2. Tenders shall be opened on the same day at **2:30 P.M** by the Contract Committee in presence of contractors who wish to be Present. Date of opening other than **30-01-2019** shall be notified on Institute web site.
3. The Tender documents will be available on the Institute website "www.nitsri.ac.in or [www.nitsri.net](http://www.nitsri.net) w.e.f **22-01-2019**, the cost of downloaded tender document as shown above in the table should be deposited in J&K Bank A/C No: 039101010000106.
4. The tenders shall be received in two bid system. Envelope A (technical bid) should contain the following documents.
  - i) Copy of valid enlistment card.
  - ii) GST registration and number.
  - iii) CDR of amount shown against the Work Pledged to **Executive Engineer** NIT Srinagar.
  - iv) PAN No.
  - v) Receipt of Cost of Tender Document.
- Envelope B (price bid) should contain quantity schedule with quoted rates covered with transparent Tape. Both the envelopes should be submitted in the main envelope which should clearly indicate the name of the contractor & the name of the work for which the tender is being submitted.
6. The envelope 'B' will be entertained only if the contractor qualifies the pre-requisite condition on the basis of the documents provided in Envelope 'A'.
7. In case the last date of receipt of tenders happens to be a holiday, tenders will be received on next working day up to 12 Noon.
8. Other terms and conditions shall be available in the tender document/Qty schedule.

**(DEAN P&D)  
N.I.T. Srinagar**

NO: NIT/P&D/2019/114-18

DT: 21-01-2019

**Copy to:-**

1. Institute Website in charge with the request to get the N.I.T up loaded in the Web Sites.
2. Ex. Engineer/Associate Dean NIT Srinagar for information please.
3. Deputy Registrar (Accounts) for information please.
4. Assistant Executive Engineer for information please.
5. P.A to Director for information of the Director please.

**Quantity Schedule /Advertised Rate list for the work of "Construction of Shed (20'x40') for Kitchen in Pre-fab hostel."  
(Adv. Cost Rs. 14.45 lacs)**

S.No.	Description of Item	Rate to be quoted by the Contractor (%)
01	Contractor may quote single percentage of rate above or below (Appreciation/depreciation) over advertised cost neatly in figures as well as in words. Items to be executed are given below in the Table.	

**List of Items to be executed**

S. No	Item Description	Qty	Rate
01.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of Soil	18 cum	125.95
02.	Providing & laying of stone soling hand packed 75mm thick including all mechanical and manual carriages up to the site.	39 cum	1000.00
03.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate <b>20 mm</b> nominal size).	19.32 cum	4927.00
04.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate <b>20 mm</b> nominal size).	11.21 cum	5481.95
05.	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns.	47.40 sqm	193.95
06.	<b>15 mm</b> cement plaster on the rough side of single or half brick wall of mix: 1:6 (1 cement: 6 fine sand).	25.79 sqm	185.20
07.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. <b>40 mm</b> thick with <b>20 mm</b> nominal size stone aggregate.	82.92 sqm	262.60
08.	Providing & fixing G.I pipes as vertical posts including cutting, hoisting, welding etc.	54.88 Rm	750.00
09.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4181 Kg	67.60
10.	Providing corrugated poly coated G.I sheets roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter. (0.50mm thick).	420.26 sqm	950.00
11.	Providing & fixing G.S sheet polymere colored Eves boarding. (0.50mm thick).	46.44 Rm	250.00
12.	Providing & fixing of 450 mm wide plain G.S sheet polymere colored ornamental for ridge.	19.51 Rm	220.00
13.	Providing and fixing of Welded mesh wherever required of specified size including cost beading and nails complete.	111.50 Kg	110.00
14.	Providing wood work in frames of doors, windows and clerestory windows and other frames wrought framed and fixed in position. <b>1<sup>st</sup> class Deodar wood</b>	0.85 cum	95000.00
15.	Providing and fixing 35 mm thick glazed shutters for windows and clerestory windows using 10 kg/Sqm. (4mm thick) glass panes including black enameled ISI marked M.S. but hinges with necessary screws. <b>Ist Class Kail Wood</b>	15.80 sqm	2800.00
16.	Providing and fixing 35 mm thick wire gauze shutters using galvanized M.S. wire gauze of average width for aperture 1.4 mm with wire of dia. 0.63 mm for doors, windows and clerestory windows including ISI marked bright finished or/and black enameled M.S. butt hinges with necessary screws. <b>Ist Class Kail Wood</b>	15.80 sqm	3000.00
17.	Providing and fixing 35 mm thick paneled door shutters, including ISI marked black enameled M.S butt hinges with necessary screws including paneling of 12mm thick decorative Nova pan board both sides laminated as per the approved design complete with required beading/moldings. (styles and rails shall be of standard size) <b>Ist Class Kail Wood</b>	3.72 sqm	4000.00
18.	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	55.76 sqm	34.95
19.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	55.76 sqm	78.40
20.	<b>Hardware items</b>		
	<b>I.</b> Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to	96 No's	49.20

	<i>required colour or shade, with necessary screws etc. complete : 100x10 mm</i>		
	<b>II. Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm</b>	02 No's	64.30
	<b>III. Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm</b>	48 No's	45.10
	<b>IV. Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16 mm</b>	01 No.	189.20
21.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron)	126 Kgs	384.50
22.	Providing and fixing <b>12 mm</b> thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides	10.04 sqm	866.60
23.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of <b>5.50 mm</b> thickness.	6.69 sqm	1003.95
24.	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall : <b>15 mm</b> dia nominal bore.	10 Rm	285.70
25.	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall: <b>20 mm</b> dia nominal bore.	30 Rm	316.20
26.	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : <b>20 mm</b> nominal bore	02 No's	396.55
27.	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : <b>15 mm</b> nominal bore	02 No's	250.00
28.	Providing and fixing Stainless Steel A ISi 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug <b>40 mm</b> , including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board <b>610x460 mm</b> bowl depth <b>200 mm</b> .	01 No.	2186.25
29.	Providing and fixing of <b>15mm</b> size chromium plated cast brass <b>sink mixer</b> of approved quality/Mark/Cera).	01 No.	2500.00
30.	Providing and fixing of <b>15mm</b> size chromium plated cast brass <b>wall mixer</b> Non telephonic with lead of approved quality/Mark/Cera).	01 No.	2200.00
31.	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 <b>15 mm</b> nominal bore	04 No's	475.70
32.	Providing and fixing plasticized PVC connection pipe with brass unions: <b>30 cm</b> length <b>15 mm</b> nominal bore.	04 No's	59.40
33.	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe <b>32 mm</b> dia	01 No.	73.25
34.	Providing and fixing of PVC Prince pipe (Type "B") in proper gradient in excavated trenches including jointing and refilling the excavated material complete including cost of excavation. (a) <b>100mm</b> dia. Pipe	06 rmt	400.00
35.	Providing and fixing of PVC Prince pipe (Type "B") in proper gradient in excavated trenches including jointing and refilling the excavated material complete including cost of excavation <b>150mm</b> dia. Pipe(female make)	30 rmt	650.00

36.	Providing & fixing <b>100mm</b> dia door bend (fenolex make)	02 NO.	200.00
37.	Providing & fixing <b>100mm</b> dia plain bend (fenolex make)	02 NO.	150.00
38.	Providing & fixing <b>100mm</b> dia floor trap (fenolex make)	02 NO.	200.00
39.	Construct brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) RCC top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) foundation concrete (1:4:8) inside plastering 12mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size finished with a floating coat of neat cement complete. <b>(a)</b> Outside size 90 × 90 × 60 cm deep including C.I manhole cover medium duty with frame & cover of size 45 × 45cm size. With F.P.S bricks with class designation 75 and crushed stone aggregate complete in all respects.	05 NO.	3000.00
40.	Construction of 9" thick brick masonry sump (7'x4'x4' outside dimension) in 02 chambers like septic tank to stop the residue of kitchen including 02 No. of CI cover with frame 2'x2' size Complete job.	01 NO.	12000.00
41.	Providing & fixing of water heater geyser of Venus/Bajaj/Re-cold make including 02 No. of angle valve, -fasteners with nuts & washers, CP tools & PVC connection	01 NO.	16000.00
42.	Carriage of sand from Ganderbal beyond 3.5 kms leads for total lead of 11 km by mechanical transport.	16.89 cum	139.48
43.	Carriage of stone aggregate from Athawajan beyond 3.5 kms lead for total lead 25 km by mechanical transport	30.50 cum	242.73

#### **TERMS AND CONDITIONS**

1. If any omission is found in the specification / rate of item or there is any typographical error in the rate/item, the same shall be read as per approved estimate.
2. The supply if found defective /not as per approved specifications, the item will not be accepted and will have to be replaced at the risk & cost of allottee.
3. Work has to be executed strictly in accordance with the specifications provided in the item within **30** days falling which penalty @ Rs.500/- per day shall be imposed.
4. The rates should be inclusive of all taxes/octri etc. Further taxes like GST, Income tax, Labour-cess or any other tax as required under rules shall be deducted from the bills of contractor.
5. No advance shall be paid during execution of work.
6. The rates should be written clearly and legible both in words and figures and avoid corrections. Further all rates should be covered with transparent tape.
7. The tenders will be valid for **120** days from the date of opening of tenders.
8. Defects liability period (DLP) shall be six months after completion of work which shall be considered as the defective liability period from the date of completion. During this period if any defect is found, the same are required to be rectified by the Contractor. In case the contractor fails to do so, the Engineer In charge may get these defects rectified up to its satisfaction by any other agency at the risk and cost of the original contractor. The amount/cost involved for rectification will be recovered from the security deposit or any other amount/cost involved for the original contractor. 10% bill deposit shall be retained till DLP expires.
9. The tenderer quoting "Rebate" on comparative cost or on item of rate will be rejected. Contractor should thus adjust amount within the quoted rate structure.
10. The splitting of quantity of any item i.e. quoting of more than one rate for the item is not accepted.
11. The tender must be accompanied by CDR pledged to **Ex. Engineer** NIT Srinagar for the amount shown against the work. Tenders without CDR will be straightway rejected and released CDR shall not be accepted.
12. In case the date of receipt of tender happens to be holiday, the same shall be received on the next working day up to 12 noon.
13. Only JK cement or Khyber Grade 43 shall be entertained for cement works.
14. The competent authority reserves the right to reject any tender without assigning any reason thereof.
15. All other terms and conditions shall remain the same as given in tender notice/NIT-cum-Agreement.

**Dean P&D**  
**N.I.T. Srinagar**

**ALL THE CONDITIONS ARE ACCEPTABLE TO ME**

(Signature of Contractor)

Name: \_\_\_\_\_ S/O : \_\_\_\_\_

R/O : \_\_\_\_\_ Ph. No: \_\_\_\_\_

